BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2023-24/OW/WORK_INDENT1086

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/05/2023-24 Dated: 13-12-2023

APPROVED TENDER SCHEDULE - B

Item-04

Name of Work:-Removal of silt & Repairs and maintenance of footpaths in ward no- 04 Yelahanka New Town.

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.Sri.MAHESH K C	
				Rate	Rate in words
1	Supply of Unskilled Mazdoor Heavy Labours As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	2304.00	662.44	Six Hundred SixtyTwo Paise FourtyFour Only
2	Supply of Skilled Mason or Brick layer Class-1As per orders of minimum wages Act KAE 02 LMW 2015 Dt: 06-01-2017 for emergency works.	Day	288.00	696.70	Six Hundred NinetySix Paise Seventy Only
3	Providing and laying 100mm thick pre-cast cover slabs over drains &Rain pit of width not exceeding 800 mm using M20 concrete reinforcedwith Micro Alloyed High carbon steel with 3mm - 3ply wired steel @ 2.00 kg/m2, slabs jointed in CM 1:3 proportion and nicely finished Includingproviding holes in the Cover slabs wherever necessary for easy drainageof surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	184.50	1051.02	One Thousand FiftyOne Paise Two Only
4	Providing and fixing pre cast solid cement concrete kerb stones made out of M20 witht top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork,curing, including cost of all materials, labhour, hire charges of machinery, loading, unloading, lead and lift, trasportation etc., complete. as directed by the Engineer in Charge of the work.	Nos	238.00	574.21	Five Hundred SeventyFour Paise TwentyOne Only
5	Providing and laying 60mm thick factory made cement concrete paverblock of approved shape and colour of M -30 grade made of C&D wasteby block making machine with vibratory compaction laid in requiredpattern and including over 50mm thick compacted bed of coarse sand,filling the joints with fine sand etc. all complete as per the direction ofEngineer-in-charge.	Sqm	36.24	906.05	Nine Hundred Six Paise Five Only
6	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms.	Cum	1300.00	227.87	Two Hundred TwentySeven Paise EightySeven Only
7	Providing and constructing un-reinforced plain cementconcrete pavement, thickness as per design, over a preparedsub base, with 43 grade cement or any other type as perClause 1501.2.2 M20 (Grade), coarse and fine aggregatesconforming to IS:383:2016, maximum size of coarseaggregate not exceeding 25 mm, mixed in a concrete mixerof not less than 0.2 cum capacity and appropriate weighbatcher using approved mix design, laid in approved fixedside formwork (steel channel, laying and fixing of 125 micronthick polythene film, wedges, steel plates including levellingthe formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate.	Cum	111.40	7218.94	Seven Thousand Two Hundred Eighteen Paise NinetyFour Only
8	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works.	t	2.00	48926.59	FourtyEight Thousand Nine Hundred TwentySix Paise FiftyNine Only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri.SHADAYAN(GANESH ENGINEERING WORKS)	
				Rate	Rate in words
9	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc., complete	hr	180.00	1528.96	One Thousand Five Hundred TwentyEight Paise NinetySix Only
10	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc., complete	hr	384.00	1599.17	One Thousand Five Hundred NinetyNine Paise Seventeen Only
11	Supply of Material component M-Sand - Fine for all road works.	Cum	150.00	1671.66	One Thousand Six Hundred SeventyOne Paise SixtySix Only
12	Supply of Material component Granular Aggregates of 12mm downsize for all road works.	Cum	120.00	1509.70	One Thousand Five Hundred Nine Paise Seventy Only
13	Supply of Material component Granular Aggregates of 20mm downsize for all road works	Cum	100.00	1509.70	One Thousand Five Hundred Nine Paise Seventy Only
14	Supply of Material component Granular Aggregates of 40mm downsize for all road works.	Cum	100.00	1347.75	One Thousand Three Hundred FourtySeven Paise SeventyFive Only
15	Supply of Material component Cement (OPC/PPC/PSC) for all road works.	Nos	450.00	331.84	Three Hundred ThirtyOne Paise EightyFour Only
16	Provision for tool - Equipments (Masonry Trowel, Head Pan, Digging Bar, Hammer, Tamper, Hand Gloves, Rubber Boots, etc.,)	LS	1.00	25740.00	TwentyFive Thousand Seven Hundred Fourty Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE - 560064